EQUIP. TAG	98XX5501
EQUIP. NAME	MGPS
CAPACITY	2000 m3/h @ 0.5ppm
CONFIGURATION	1 x 100%
WORKING/DESIGN PRESSURE	2 / 8 BARG
WORKING/DESIGN TEMP.	°C
DUTY POWER	12.5 kW kW
MATERIAL	-

98XX5501 INTERFACES		
TP	DESCRIPTION	CONNECTION TYPE / SIZE
TP01	SEAWATER INLET	1 1/2" 150# FF
TP02	INSTRUMENT AIR INLET	1/4" NPTF
TP03	DISCHARGE TO SC (PORT)	1 1/2" 150# FF
TP04	DISCHARGE TO SC (STBD)	1 1/2" 150# FF
TP05	DISCHARGE TO FIREWATER SC	1 1/2" 150# FF
TP06	DISCHARGE TO BALLAST SC	1 1/2" 150# FF

SYSTEM PARAMETERS		
SERVICE	MGPS	INSTRUMENT AIR
DESIGN PRESSURE(Barg)	7.0	11.5
OPERATING PRESSURE(Barg)	2.8	10.0
DESIGN TEMPERATURE(°C)	50.0	50.0
OPERATING TEMPERATURE,(°C)	29.3	AMB

R02

COMMON FAULT ALARM — 98 VMS XX 5501 XA
RUNNING INDICATION — 98 VMS XX 5501 XL1
REMOTE CURRENT INDICATION — 98 VMS XX 5501 IL1
REMOTE CURRENT SET — 98 VMS XX 5501 IL2
SEA CHEST (PORT) VALVE OPEN — 98 VMS XX 5501 HS1
SEA CHEST (STBD) VALVE OPEN — 98 VMS XX 5501 HS2
FIRE WATER SEA CHEST VALVE OPEN — 98 VMS XX 5501 HS3
BALLAST SEA CHEST VALVE OPEN — 98 VMS XX 5501 HS4
LOCAL/REMOTE CURRENT CONTROL MODE — 98 VMS XX 5501 XL2

LCP
98XX5501-EC01
NOTE 3

SEA WATER SUPPLY
GOE-FHM-MR-PID-105030
0384-KEP-V-XB-51002.001
51-2"-WS-G3-5518
2"x1 1/2"
TP 01
98BAV5801
98 SP 5801
98BAV5802
98 FIT 5801
FIT
98BAV5803
ELECTROLYSER ASSEMBLY
AIR VENT
98 LSH 5801
98BAV5805
1 1/2"
98BAV5804 1"x1 1/2"
R02

INSTRUMENT AIR SUPPLY
GOE-FHM-MR-PID-105107
0384-KEP-V-XB-67002.001
67-1/2"-AI-G1-5748
1/2"x1/4"
TP02
98BAV5814
98 PCV 5801
98 PSV 5801
1/4" SUS TUBING

98-XX-5501
NOTE 1,2

98 XY 5801 S
98 XV 5801 P
98 FI 5801 FI
2"x1 1/2"
TP03
98-1 1/2"-WS-G9-5512
MAIN SEA CHEST (PORT)
GOE-FHM-MR-PID-105030
0384-KEP-V-XB-51002.001
98DPV5801 1 1/2"x2"

98 XY 5802 S
98 XV 5802 P
98 FI 5802 FI
2"x1 1/2"
TP04
98-1 1/2"-WS-G9-5513
MAIN SEA CHEST (STBD)
GOE-FHM-MR-PID-105030
0384-KEP-V-XB-51002.001
98DPV5802 1 1/2"x2"

98 XY 5803 S
98 XV 5803 P
98 FI 5803 FI
2"x1 1/2"
TP05
98-1 1/2"-WS-G9-5510
FIRE WATER SEA CHEST
GOE-FHM-MR-PID-105116
0384-KEP-V-XB-71001.001
98DPV5803 1 1/2"x2"

98 XY 5804 S
98 XV 5804 P
98 FI 5804 FI
2"x1 1/2"
TP06
98-1 1/2"-WS-G9-5511
BALLAST SEA CHEST
GOE-FHM-MR-PID-105001
0384-KEP-V-XB-52001.001
R02
98DPV5804 1 1/2"x2"

GENERAL NOTES:

1. THIS P&ID IS REISSUED FOR INFORMATION FOR SAKARYA PROJECT.
2. NO CHANGE IN SYSTEM.
3. FOR P&ID LEGEND SHEET SEE DRAWING: SC26-2A-GOE-FGN-PE-PID-100018, SC26-2A-GOE-FGN-PE-PID-100021 TO 100031.
4. FOR MARINE PIPING AND VALVE MATERIAL SPECIFICATION, SEE DOCUMENT: SC26-2A-GOE-FHM-EP-SPC-105001 (4517-BWO-L-SA-00002)

R02

NOTES:

1. MGPS VENDOR SUPPLIED.
2. REFER TO VENDOR P&ID 0384-EIC-V-XB-98001.001.
3. FOR SIGNALS BETWEEN ICSS AND VENDOR PACKAGE, REFER TO 0384-KEP-I-LA-00008.

HOLDS:

1. DELETED. R02

LEGENDS:

EXISTING PIPE

R02

GOE REV.	OTC REV.	REASON FOR USE	DATE	DRAWN	ISSUED	CHECKED	APPROVED
-	R02	ISSUED FOR INFORMATION	02/09/25	ZYL	DWJ	DC	SJL
-	R01	ISSUED FOR INFORMATION	07/05/25	ZYL	DWJ	DC	SJL
-	R00	ISSUED FOR INFORMATION (1st GOE ISSUE)	23/12/24	ZYL	DWJ	DC	SJL
Z1	-	RE-ISSUED FOR AS-BUILT	27/01/23	EM	ADB	NO	BL
Z0	-	ISSUED FOR AS-BUILT	28/09/22	JT	JT	NO	BL
03	-	RE-ISSUED FOR CONSTRUCTION	08/04/21	XH	JT	NO	BL
02	-	RE-ISSUED FOR CONSTRUCTION	11/06/20	XH	JT	NO	BL
01	-	RE-ISSUED FOR CONSTRUCTION	09/04/20	XH	JT	NO	BL
00	-	ISSUED FOR CONSTRUCTION	08/11/19	XH	JT	NO	BL
D	-	RE-ISSUED FOR DESIGN	05/07/19	XH	JT	NO	BL
C	-	ISSUED FOR DESIGN	17/05/19	CW	JT	NO	PL
B	-	ISSUED FOR APPROVAL	05/04/19	TL	JT	NO	PL
A	-	ISSUED FOR IDC	01/03/19	TL	JT	NO	PL

DISCIPLINE:	SYSTEM NO:	AREA / MODULE:	IMO NO:	PROJECT NO:	SCALE:	SIZE:
MR	51	FHM	8706014	SC26-2A	N.T.S.	A3

SUPPLIER: OceanSTAR Elite — GOE GLOBAL OFFSHORE ENGINEERING

CLIENT: TP OTC OFFSHORE TECHNOLOGY CENTER

PROJECT: Sakarya Gas Field Dev't Phase-2a

TITLE: P&ID - SEA WATER MAIN HEADER AND COOLING PUMPS IN ENGINE ROOM (SHEET 2)

OTC DOC. NO:	SC26-2A-GOE-FHM-MR-PID-105079	GOE REV.	SHEET
LEG DOC. NO:	-	-	2 of 2
REF. DOC. NO:	0384-KEP-V-XB-51002.002	OTC REV. R02	

This drawing contains proprietary information and may not be transferred, reproduced or used to construct any project other than it was issued for without the written consent of GOE or their Client.

CODE 1 - Accepted without Comment - 04/10/2026 12:23:26 Internal